

PROJECT: QUOTE 20 VPD EVIDENCE/EQUIPMENT SERVICES FALL PROTECTION PROJECTS

LAKE OSWEGO CONST
5290 SW CHILDS RD
LAKE OSWEGO OR 97035
503-320-3647

HY-SAFE TECHNOLOGY
960 COMMERCE DR
UNION GROVE WI 53182
262-752-2400

QUOTE OPENING: AUGUST 14, 2014

ENGINEER'S ESTIMATE: \$40,000-50,000

Completed by 11/15/14

SCHEDULE "A" - VPD EVIDENCE BUILDING

ITEM	QUANTITY	UNIT	UNIT PRICE	AMOUNT	UNIT PRICE
1. Provide all labor, materials and testing required for a complete and approved fall restraint system at the perimeter of the upper roof and roof hatch per the scope of work plans and specifications and WAC Title 296-155-24603 for the VPD Evidence Building, 2325 W Mill Plain Blvd, Vancouver, WA 98660, per scope of work, plans, specifications, and WAC Title 296.	1.00	LS	72140.00	72140.00	Non-Responsive-wrong forms used
Schedule A Subtotal				72140.00	
8.4% Wa State Sales Tax				6059.76	
SCHEDULE A TOTAL				78199.76	

SCHEDULE "B" - EQUIPMENT SERVICES BUILDING

ITEM	QUANTITY	UNIT	UNIT PRICE	AMOUNT	UNIT PRICE
1B. Provide all labor, materials and testing required for a complete and approved fall restraint system at the perimeter of the upper roof and roof hatch per the scope of work plans and specifications and WAC Title 296-155-24603 for the Operations Equipment Services Building, 4711 E. Fourth Plain Boulevard, Vancouver, Washington 98661	1.00	LS	50451.00	50451.00	
2B. 1. Replace the roof hatch. Hatch size outside is approximately 35" x 59", inside is 30" x 54" X 12" tall. Curb size is 33" x 56-1/2". 2. Re-roof around the hatch to match existing single ply roofing. Possibly a Stevens EP material. 3. Re-weld the existing walk-off mats around the roof hatch that are loose. 4. Remove the existing metal conduit flashing at the SW corner of the building and install a split roof jack for the conduit and weld to the deck roofing as needed.	1.00	LS	8781.00	8781.00	
Schedule B Subtotal				59232.00	
8.4% Wa State Sales Tax				4975.49	
SCHEDULE B TOTAL				64207.49	

SCHEDULE "A" - VPD EVIDENCE BUILDING TOTAL	78199.76
SCHEDULE "B" - EQUIPMENT SERVICES BUILDING TOTAL	64207.49
GRAND TOTAL SCHEDULES "A" & "B"	142407.25